3.	Supplying and running 3 phase mains in 2" W.I. pipe using No. 3-0 B. and S. insulated wire and accessories	Ft. 5
4.	Supplying, fixing and wiring a teak wood board $2\frac{1}{2}" \times 3\frac{1}{2}" \times 1"$ with battens rear board, supported on a suitable angle iron frame work equipping the board with 11 single pole iron clad 60 amps. cut outs, using No. 3-0 and 4 B. and S. insulated wires and accessories	No. 1
5.	Supplying and laying No. 4 B. and S. 3-conductor, paper insulated, lead covered, double steel tape armoured, jute served underground cable, 1,000 volts pressure, in a trench 3' deep surrounding the same with 3" fine sand and enclosing the ends in indoor type junction boxes filled with insulating compound using $1\frac{1}{2}"$ W.I. pipe No. 4 B. and S. insulated wires and accessories	Ft. 260
6.	Supplying, fixing and wiring in 3-way teakwood casing treated with two coats of Shellac varnish for switch points using D.P. 30 amps. iron clad switch with fuses, $12" \times 12" \times 1"$ teak wood board with back board, battens, No. 6 and 8 B. and S. Megohms grade insulated wires for main and tap respectively	No. 6
7.	Do do for D.P. 20 amps. iron clad switches as per specification above	„ 3
8.	Do do for Instantaneous Water Heaters, 40 amp. with nickle plated bends, back plate, etc., controlled by a 30 amp. D.P. iron clad switch with fuses mounted on a suitable T.W. board, etc., using No. 8 B. and S. 2,500 Megohms grade insulated wire .. .. (Instantaneous Water Heater will be supplied departmentally.)	
9.	Supply of Heater cord No. 10 B. and S. Twin asbestos covered and braided.	Ft. 120
10.	Earthing	L.S.

M. HAYATH,
Superintendent.

MYSORE RAILWAYS.

OFFICE OF THE CHIEF STORE-KEEPER, MYSORE SOUTH.

Notice dated 3rd August 1937.

Tenders are invited for the purchase of one typewriter, Remington No. 12 (Firm's Sl. No. L. D. 37245), automatic ribbon movement, second-hand, in working order with base-board and cover complete. The machine may be inspected at the Railway Central Stores Depot, Mysore South, during working days between 7-30 to 11-30 A.M. and 2 to 4-30 P.M. Tenders in covers sealed and superscribed "Tender for the purchase of typewriting machine," should reach this office before 4 P.M. on 30th August 1937. Offers below Rs. 75 are not likely to receive any consideration.

A. SADASIVAN,
Chief Store-Keeper.

OFFICE OF THE ASSISTANT ENGINEER, HEADQUARTER RANGE, MYSORE.

Notification dated 14th August 1937.

1. Sealed tenders will be received at the Office of the Assistant Engineer, Headquarter Range Mysore, upt o 12 NOON on 27th August 1937, for constructing Seetha-Ranga Out-Patient Dispensary for the New Cheluvamba Maternity Hospital, Mysore.

2. Tenders in the prescribed form obtainable from the Office of the Assistant Engineer, Headquarter Range, Mysore, on payment of rupee one for each form, should be addressed to the Assistant Engineer, Headquarter Range, and should be superscribed as "Tender for constructing Seetha-Ranga Out-Patient Dispensary for the New Cheluvamba Maternity Hospital at Mysore." The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 1,000 only in cash or Government Security, Municipal Debentures, Post Office Cash Certificates, (at cash payment value at the time of deposits and not face value) as earnest money. The earnest money of the successful tenderer will be retained as cash security for the due fulfilment of the contract. (Cash amount will not carry any interest.) In case of the acceptance of the tender, an addition of the five per cent of the estimated amount as security deposit should be paid at the time of executing the agreement in the Public Works Department Form.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 27th August 1937, at 4 P.M. The final acceptance of the tender will rest with the Superintending Engineer who does not bind himself to accept the lowest or any tender, or to assign any reasons whatever, for the rejection of any.